

**Angelo Gioia- Excavation/Construction
Contractors**

**602 Rosehill Rd
Broomall, PA 19008**

Proposal

Date	Proposal #
3/31/2018	14222

Name / Address
Eric Hoffman 131 Cynwyd Rd. Bala Cynwyd Pa 19004

			Project
Description	Qty	Rate	Total
Concrete Sidewalk & Curb: Remove existing sections of sidewalk and curb as per plan, form and pour new concrete curb 20in x 6in and sidewalk 6in over 4in of 2B stone with 6x6 WWF, excavate area where new asphalt is to be placed, stone area with 10in of 2A, pave with 8in of BCBC, 3in of asphalt binder and 2in of ID-2 asphalt top course, tar seams with AC-20 hot tar filler, remove all demo and unused material from site		6,400.00	6,400.00
Total			\$6,400.00

Phone #	Fax #
610-587-6345	484-422-8874