

TOWNSHIP OF LOWER MERION
TABULATION OF BIDS: CONCRETE CURB, SIDEWALKS AND RAMPS
CONTRACT NUMBER: 4211, 4215, 4405, 4458-20-15
BIDS RECEIVED: OCTOBER 15, 2020 - 11:00 AM

Item #	Bidders:	Hamilton Contractors, Inc.			Donato Spaventa & Sons, Inc.			Albert G. Cipolloni Jr. & Sons, Inc.			MOR Construction Services			Ettore Ventresca & Sons, Inc.		
	Description	Qty	Unit Price	Total	Qty	Unit Price	Total	Qty	Unit Price	Total	Qty	Unit Price	Total	Qty	Unit Price	Total
1	4" Plain cement concrete sidewalk including saw cutting, removal of existing sidewalk and debris, unit price per sq. ft.	4,250	\$ 13.39	\$ 56,907.50	4,250	\$ 13.25	\$ 56,312.50	4,250	\$ 13.85	\$ 58,862.50	4,250	\$ 15.00	\$ 63,750.00	4,250	\$ 15.00	\$ 63,750.00
1A	4" Plain cement concrete sidewalk including preparation of foundation. (No breaking out or removal Necessary); unit price per sq. ft.	200	\$ 13.39	\$ 2,678.00	200	\$ 12.75	\$ 2,550.00	200	\$ 12.00	\$ 2,400.00	200	\$ 13.00	\$ 2,600.00	200	\$ 11.00	\$ 2,200.00
2	6" Reinforced cement concrete OR 7" plain cement concrete sidewalk, including saw cutting, removal of existing sidewalk and debris; unit price per sq. ft.	200	\$ 13.39	\$ 2,678.00	200	\$ 15.25	\$ 3,050.00	200	\$ 14.95	\$ 2,990.00	200	\$ 16.00	\$ 3,200.00	200	\$ 25.00	\$ 5,000.00
2A	6" Reinforced cement concrete OR 7" plain cement sidewalk, including preparation of foundation. (No breaking out or removal necessary); unit price per sq. ft.		\$ 16.80			\$ 14.75			\$ 13.45			\$ 14.00			\$ 20.00	
3	6" x 18" Plain cement concrete curb including saw cutting, removal of existing curb and debris, unit price per l.f.	20	\$ 72.10	\$ 1,442.00	20	\$ 110.00	\$ 2,200.00	20	\$ 70.00	\$ 1,400.00	20	\$ 55.00	\$ 1,100.00	20	\$ 78.00	\$ 1,560.00
3A	6" x 18" Plain cement concrete curb including preparation of foundation. (no breaking out or removal necessary) unit price per l.f.		\$ 85.00			\$ 105.00			\$ 60.00			\$ 50.00			\$ 50.00	
4	Installation of Curb Cut Ramps, (ADA Compliant Handicap Ramps) 4" concrete sidewalk		\$ 15.88			\$ 21.00			\$ 25.00			\$ 25.00			\$ 15.00	
	7" concrete sidewalk - unit price per sq. ft.		\$ 15.88			\$ 26.00			\$ 30.00			\$ 26.00			\$ 25.00	
	6" x 18" concrete curb - unit price per l.f.		\$ 90.00			\$ 110.00			\$ 80.00			\$ 75.00			\$ 80.00	
	2' x 4' Dome Warning Tiles - unit price per tile		\$ 350.00			\$ 400.00			\$ 300.00			\$ 250.00			\$ 270.00	
5	Installation and/or Resetting of Granite Curb including saw cutting, removal of existing curb and debris; unit price per l.f. Note: Granite curb to be supplied by Township. Contractor to pick up Granite Curbing at Township Public Works Complex	20	\$ 72.10	\$ 1,442.00	20	\$ 120.00	\$ 2,400.00	20	\$ 80.00	\$ 1,600.00	20	\$ 135.00	\$ 2,700.00	20	\$ 79.00	\$ 1,580.00
6	Concrete steps with 7" or 8" riser in place, including removal of existing steps; unit price per cubic yard		\$ 900.00			\$ 3,125.00			\$ 1,850.00			\$ 295.00			\$ 1,650.00	
7	Installation of screened topsoil with seed and soil supplements Formula B: unit price per cubic yard	20	\$ 51.50	\$ 1,030.00	20	\$ 98.00	\$ 1,960.00	20	\$ 80.00	\$ 1,600.00	20	\$ 70.00	\$ 1,400.00	20	\$ 160.00	\$ 3,200.00
8	Installation of 4" roof drain under sidewalk and through curb including welded wire fabric over drain and any needed saw cutting, unit price per l.f.		\$ 400.00			\$ 248.00			\$ 70.00			\$ 200.00			\$ 32.00	
9	Installation of Parking Meter Posts supplied by the Township and set to proper grade and specifications. See Exhibit "F" - unit price per post		\$ 250.00			\$ 302.00			\$ 260.00			\$ 500.00			\$ 740.00	
10	Road Restoration: This item shall include the excavation of temporary paving and one foot cut back to a depth of 7 inches, compaction of sub-grade, installation of 6 inches of bituminous concrete base course compacted in two 3 inch layers and 1 inch of ID-2A surface course. The edge and area abutting the curb then shall be sealed with AC-20 bituminous sealer. All materials used in the restoration must meet the specifications of PennDOT Form 408 - unit price per sq. yd.	15	\$ 111.24	\$ 1,668.60	15	\$ 120.00	\$ 1,800.00	15	\$ 130.00	\$ 1,950.00	15	\$ 150.00	\$ 2,250.00	15	\$ 74.00	\$ 1,110.00
11	Driveway Restoration: This item shall include the excavation of temporary paving and one foot cut back to a depth of 2 inches, compaction of sub-grade, installation of a full 2 inches of ID-2 surface course to bring the area to meet existing grade of the driveway and new sidewalk; unit price per sq. yd.	15	\$ 74.16	\$ 1,112.40	15	\$ 120.00	\$ 1,800.00	15	\$ 120.00	\$ 1,800.00	15	\$ 89.00	\$ 1,335.00	15	\$ 41.00	\$ 615.00
	Total Bid Amount			\$ 68,958.50			\$ 72,072.50			\$ 72,602.50			\$ 78,335.00			\$ 79,015.00

TOWNSHIP OF LOWER MERION
TABULATION OF BIDS: CONCRETE CURB, SIDEWALKS AND RAMPS
CONTRACT NUMBER: 4211, 4215, 4405, 4458-20-15
BIDS RECEIVED: OCTOBER 15, 2020 - 11:00 AM

Bidders:		Ocean Construction, LLC			T. Schiefer Contractors, Inc.			The Vanic Company, Inc.			Delaware Valley Paving			McCarthy Masonry & Concrete, Inc.		
Item #	Description	Qty	Unit Price	Total	Qty	Unit Price	Total	Qty	Unit Price	Total	Qty	Unit Price	Total	Qty	Unit Price	Total
1	4" Plain cement concrete sidewalk including saw cutting, removal of existing sidewalk and debris, unit price per sq. ft.	4,250	\$ 16.00	\$ 68,000.00	4,250	\$ 16.00	\$ 68,000.00	4,250	\$ 15.00	\$ 63,750.00	4,250	\$ 16.50	\$ 70,125.00	4,250	\$ 19.00	\$ 80,750.00
1A	4" Plain cement concrete sidewalk including preparation of foundation. (No breaking out or removal Necessary); unit price per sq. ft.	200	\$ 12.00	\$ 2,400.00	200	\$ 15.00	\$ 3,000.00	200	\$ 12.00	\$ 2,400.00	200	\$ 13.20	\$ 2,640.00	200	\$ 23.00	\$ 4,600.00
2	6" Reinforced cement concrete OR 7" plain cement concrete sidewalk, including saw cutting, removal of existing sidewalk and debris; unit price per sq. ft.	200	\$ 19.00	\$ 3,800.00	200	\$ 19.00	\$ 3,800.00	200	\$ 17.50	\$ 3,500.00	200	\$ 18.70	\$ 3,740.00	200	\$ 28.00	\$ 5,600.00
2A	6" Reinforced cement concrete OR 7" plain cement sidewalk, including preparation of foundation. (No breaking out or removal necessary); unit price per sq. ft.		\$ 17.00			\$ 18.00			\$ 15.00			\$ 15.40			\$ 25.00	
3	6" x 18" Plain cement concrete curb including saw cutting, removal of existing curb and debris, unit price per l.f.	20	\$ 110.00	\$ 2,200.00	20	\$ 88.00	\$ 1,760.00	20	\$ 75.00	\$ 1,500.00	20	\$ 82.50	\$ 1,650.00	20	\$ 130.00	\$ 2,600.00
3A	6" x 18" Plain cement concrete curb including preparation of foundation. (no breaking out or removal necessary) unit price per l.f.		\$ 50.00			\$ 85.00			\$ 65.00			\$ 66.00			\$ 75.00	
4	Installation of Curb Cut Ramps, (ADA Compliant Handicap Ramps) 4" concrete sidewalk		\$ 22.00			\$ 24.00			\$ 21.00			\$ 2,750.00			\$ 19.50	
	7" concrete sidewalk - unit price per sq. ft.		\$ 28.00			\$ 30.00			\$ 25.00			\$ 2,860.00			\$ 24.00	
	6" x 18" concrete curb - unit price per l.f.		\$ 118.00			\$ 100.00			\$ 125.00			\$ 2,750.00			\$ 108.00	
	2' x 4' Dome Warning Tiles - unit price per tile		\$ 225.00			\$ 350.00			\$ 375.00			\$ 3,080.00			\$ 350.00	
5	Installation and/or Resetting of Granite Curb including saw cutting, removal of existing curb and debris; unit price per l.f. Note: Granite curb to be supplied by Township. Contractor to pick up Granite Curbing at Township Public Works Complex	20	\$ 186.00	\$ 3,720.00	20	\$ 80.00	\$ 1,600.00	20	\$ 80.00	\$ 1,600.00	20	\$ 55.00	\$ 1,100.00	20	\$120.00	\$ 2,400.00
6	Concrete steps with 7" or 8" riser in place, including removal of existing steps; unit price per cubic yard		\$ 1,200.00			\$ 1,800.00			\$ 750.00			\$ 770.00			\$ 4,380.00	
7	Installation of screened topsoil with seed and soil supplements Formula B: unit price per cubic yard	20	\$ 65.00	\$ 1,300.00	20	\$ 120.00	\$ 2,400.00	20	\$ 75.00	\$ 1,500.00	20	\$ 55.00	\$ 1,100.00	20	\$ 221.90	\$ 4,438.00
8	Installation of 4" roof drain under sidewalk and through curb including welded wire fabric over drain and any needed saw cutting, unit price per l.f.		\$ 28.00			\$ 150.00			\$ 45.00			\$ 71.50			\$ 16.35	
9	Installation of Parking Meter Posts supplied by the Township and set to proper grade and specifications. See Exhibit "F" - unit price per post		\$ 500.00			\$ 350.00			\$ 50.00			\$ 125.00			\$ 212.55	
10	Road Restoration: This item shall include the excavation of temporary paving and one foot cut back to a depth of 7 inches, compaction of sub-grade, installation of 6 inches of bituminous concrete base course compacted in two 3 inch layers and 1 inch of ID-2A surface course. The edge and area abutting the curb then shall be sealed with AC-20 bituminous sealer. All materials used in the restoration must meet the specifications of PennDOT Form 408 - unit price per sq. yd.	15	\$ 67.50	\$ 1,012.50	15	\$ 125.00	\$ 1,875.00	15	\$ 225.00	\$ 3,375.00	15	\$ 200.00	\$ 3,000.00	15	\$ 175.00	\$ 2,625.00
11	Driveway Restoration: This item shall include the excavation of temporary paving and one foot cut back to a depth of 2 inches, compaction of sub-grade, installation of a full 2 inches of ID-2 surface course to bring the area to meet existing grade of the driveway and new sidewalk; unit price per sq. yd.	15	\$ 20.00	\$ 300.00	15	\$ 125.00	\$ 1,875.00	15	\$ 509.00	\$ 7,635.00	15	\$ 175.00	\$ 2,625.00	15	\$ 175.00	\$ 2,625.00
	Total Bid Amount			\$ 82,732.50			\$ 84,310.00			\$ 85,260.00			\$ 85,980.00			\$ 105,638.00

TOWNSHIP OF LOWER MERION
TABULATION OF BIDS: CONCRETE CURB, SIDEWALKS AND RAMPS
CONTRACT NUMBER: 4211, 4215, 4405, 4458-20-15
BIDS RECEIVED: OCTOBER 15, 2020 - 11:00 AM

Item #	Bidders:	JPS Construction Company			Construction Masters Services, LLC			DePaul and Company, Inc.			Road-Con, Inc.		
	Description	Qty	Unit Price	Total	Qty	Unit Price	Total	Qty	Unit Price	Total	Qty	Unit Price	Total
1	4" Plain cement concrete sidewalk including saw cutting, removal of existing sidewalk and debris, unit price per sq. ft.	4,250	\$ 15.00	\$ 63,750.00	4,250	\$ 26.08	\$ 110,840.00	4,250	\$ 32.00	\$ 136,000.00	4,250	\$ 55.00	\$ 233,750.00
1A	4" Plain cement concrete sidewalk including preparation of foundation. (No breaking out or removal Necessary); unit price per sq. ft.	200	\$ 30.00	\$ 6,000.00	200	\$ 18.73	\$ 3,746.00	200	\$ 27.00	\$ 5,400.00	200	\$ 49.00	\$ 9,800.00
2	6" Reinforced cement concrete OR 7" plain cement concrete sidewalk, including saw cutting, removal of existing sidewalk and debris; unit price per sq. ft.	200	\$ 40.00	\$ 8,000.00	200	\$ 27.21	\$ 5,442.00	200	\$ 34.00	\$ 6,800.00	200	\$ 56.00	\$ 11,200.00
2A	6" Reinforced cement concrete OR 7" plain cement sidewalk, including preparation of foundation. (No breaking out or removal necessary); unit price per sq. ft.		\$ 50.00			\$ 18.73			\$ 45.00			\$ 56.00	
3	6" x 18" Plain cement concrete curb including saw cutting, removal of existing curb and debris, unit price per l.f.	20	\$ 100.00	\$ 2,000.00	20	\$ 142.09	\$ 2,841.80	20	\$ 120.00	\$ 2,400.00	20	\$ 325.00	\$ 6,500.00
3A	6" x 18" Plain cement concrete curb including preparation of foundation. (no breaking out or removal necessary) unit price per l.f.		\$ 100.00			\$ 106.39			\$ 180.00			\$ 320.00	
4	Installation of Curb Cut Ramps, (ADA Compliant Handicap Ramps) 4" concrete sidewalk		\$ 15.00			\$ 26.08			\$ 300.00			\$ 50.00	
	7" concrete sidewalk - unit price per sq. ft.		\$ 40.00			\$ 27.22			\$ 360.00			\$ 52.00	
	6" x 18" concrete curb - unit price per l.f.		\$ 100.00			\$ 269.93			\$ 248.00			\$ 320.00	
	2' x 4' Dome Warning Tiles - unit price per tile		\$ 1,000.00			\$ 619.63			\$ 350.00			\$ 450.00	
5	Installation and/or Resetting of Granite Curb including saw cutting, removal of existing curb and debris; unit price per l.f. Note: Granite curb to be supplied by Township. Contractor to pick up Granite Curbing at Township Public Works Complex	20	\$ 200.00	\$ 4,000.00	20	\$ 25.08	\$ 501.60	20	\$ 290.00	\$ 5,800.00	20	\$ 325.00	\$ 6,500.00
6	Concrete steps with 7" or 8" riser in place, including removal of existing steps; unit price per cubic yard		\$ 4,000.00			\$ 1,789.27			\$ 1,429.00			\$ 2,050.00	
7	Installation of screened topsoil with seed and soil supplements Formula B; unit price per cubic yard	20	\$ 150.00	\$ 3,000.00	20	\$ 96.42	\$ 1,928.40	20	\$ 100.00	\$ 2,000.00	20	\$ 280.00	\$ 5,600.00
8	Installation of 4" roof drain under sidewalk and through curb including welded wire fabric over drain and any needed saw cutting, unit price per l.f.		\$ 2,000.00			\$ 652.81			\$ 500.00			\$ 384.00	
9	Installation of Parking Meter Posts supplied by the Township and set to proper grade and specifications. See Exhibit "F" - unit price per post		\$ 4,500.00			\$ 621.36			\$ 467.00			\$ 2,070.00	
10	Road Restoration: This item shall include the excavation of temporary paving and one foot cut back to a depth of 7 inches, compaction of sub-grade, installation of 6 inches of bituminous concrete base course compacted in two 3 inch layers and 1 inch of ID-2A surface course. The edge and area abutting the curb then shall be sealed with AC-20 bituminous sealer. All materials used in the restoration must meet the specifications of PennDOT Form 408 - unit price per sq. yd.	15	\$ 1,000.00	\$ 15,000.00	15	\$ 108.70	\$ 1,630.50	15	\$ 260.00	\$ 3,900.00	15	\$ 495.00	\$ 7,425.00
11	Driveway Restoration: This item shall include the excavation of temporary paving and one foot cut back to a depth of 2 inches, compaction of sub-grade, installation of a full 2 inches of ID-2 surface course to bring the area to meet existing grade of the driveway and new sidewalk; unit price per sq. yd.	15	\$ 500.00	\$ 7,500.00	15	\$ 87.55	\$ 1,313.25	15	\$ 236.00	\$ 3,540.00	15	\$ 495.00	\$ 7,425.00
	Total Bid Amount			\$ 109,250.00			\$ 128,243.55			\$ 165,840.00			\$ 288,200.00